

Cost Working/Estimate

Name of Company:	Pfizer limited Goa	Estimate No:	006
Location/Site:	Verna S.O	Estimate Date:	09/06/2025
Nature of Work:	flooring Coating	Revision No:	R002
Technology Used:	Poly Ironite Ceramic Cementitious Epoxy Coating(90:10)	Revision Date:	10/06/2025
Area (In Sq. Mtr.):	25		
Thickness in mm:			

S.N.	Item	HSN Code	Qty/M²	Unit	Qty. for Total Area (in SqM)	Std Pak	Basic Rate	Basic Amount
A-	Material Cost							
1	Surface Cleaning							
	Steripure S 30	340290	0.01	Ltr	0.00	1	1864.00	466.00
2	Bond Coat							
	Kelox R101	390720	0.30	Kg	8.00	20	1400.00	10500.00
3								
	Kelox H 404	390720	0.15	Kg	4.00	10	1400.00	5250.00
4	PICC Epoxy 90:10 Coating (5mm)							
	Nicomix WP	382450	6.21	Kg	155.00	30	120.00	18630.00
5								
	Cement 53G	252329	3.62	Kg	91.00	50	10.00	906.00
6								
	test346	382450	0.52	Kg	13.00		0.00	0.00
7								
	PICC Epoxy Rex	390720	0.77	Kg	19.00	20	1400.00	26852.00
8								
	PICC Epoxy HD	390720	0.38	Kg	10.00	10	1400.00	13440.00
Total Material Basic Cost						A	Rs.	76044.00
Per Sq. Mtr. Material Cost						A	Per Sq Mtr.	3041.76

	Description	Area	Unit	Amount
B-	Cost as per project / Site condition			
B1-				
	Labour cost	25.00	M2	10000.00
	Consumable cost	25.00	M2	1250.00

	Description	Area	Unit	Amount
B-	Cost as per project / Site condition			
	Transport cost	25.00	M2	500.00
	Supervision cost	25.00	M2	750.00
	B1 - Total:	100.00		12500.00
B2				
	Finance cost	6.00	1.00%	5312.64
	Total Cost:	b2	M2	17812.64
B3				
	Over Head Charges	0.00	20.00%	3562.528
	Total application (Labour) cost:	=(B1+B2+B3)	M2	21375.17

	Total	Unit	Qty	Total Project Cost Rs
C-	Project Calculation			
	Total Material Basic Cost	A	M2	76044.00
	Total application (Labour) cost	B	M2	21375.17
	Total Material + Application basic Cost	A+B	M2	97419.17
	Contractor profit	C	20.00	19483.83
	Total Project Cost :	A+B+C		116903.00
	Total Project Cost Per M2 :	M2		4676.12

Note

Notes:

Above rates are ex-factory. Transport to be arrange by you at your cost
 Material Supply will be as per standard packing.
 Variation in std. packing may result in change of product price.
 Qty may vary depend upon surface / cavity etc. Condition / applicator.
 Payment 100 % advance.
 GST 18% extra or as applicable
 Application Cost is Extra at client Scope
 Transit insurance from our factory to your location is to be borne by you.

For Dimple Chemicals & Services Pvt. Ltd.

Approved By	Checked By	DCPL Representative	Prepared By